

4. NORMAL PROCEDURES

4.1 PREFLIGHT CHECK

- | | |
|------------------------|--|
| Fuel jettison manifold | – Installed, no leaks |
| Nozzle extension | – Installed as required (see Para 2.2) |
| FUEL JETT switch | – Guarded, breakaway safety-wired |

5. PERFORMANCE DATA

NOTE A reduction of 100 kg (220 lb) fuel will improve the OEI rate-of-climb by approx 100 fpm at V_Y .